

TRISH & ALLEN UNDERWOOD

LOT 62 MAGNOLIA SHORES Custom Home




SHEET INDEX:

- B1 - COVER SHEET*
- B2 - FLOOR PLAN*
- B3 - ELEVATIONS*
- B4 - ELEVATIONS*
- B5 - FOUNDATION PLAN*
- B6 - ROOFING PLAN*
- B7 - DETAILS*
- B8 - GENERAL NOTES*

NO.	DESCRIPTION	BY	DATE

SHEET TITLE:

PROJECT DESCRIPTION:
UNDERWOOD HOME
Lot 62 Leigh Rd
Washington, NC 27889

DRAWINGS PROVIDED BY:

HORTON CUSTOM DESIGNS


DATE:

1/3/23

SCALE:

SHEET:

B-1



FIRST FLOOR PLAN

DOOR SCHEDULE		
NUMBER	QTY	SIZE
D01	1	1468 R IN
D02	1	2668 R
D03	1	2668 R IN
D04	1	2868 L
D05	1	2868 R IN
D06	3	3068 L EX
D07	3	3068 L IN
D08	1	3068 R
D09	2	3068 R IN
D10	1	4068 L/R EX
D11	3	4068 L/R IN
D12	1	58710
D13	2	9080


WINDOW SCHEDULE		
NUMBER	SIZE	QTY
W01	2446DH	2
W02	2830DH	1
W03	2840DH	1
W04	2852DH	4
W05	2856DH	4
W06	2860DH	3
W07	4010FX	1

FLOOR AREAS:
 1ST FLOOR HEATED - 1794 SF
 FRONT PORCH - 160 SF
 GARAGE - 574 SF
 REAR PORCH - 181 SF

NO.	DESCRIPTION	BY	DATE

SHEET TITLE:
FLOOR PLAN


PROJECT DESCRIPTION:
UNDERWOOD HOME
 Lot 62 Leigh Rd
 Washington, NC 27889

DRAWINGS PROVIDED BY:

HORTON CUSTOM DESIGNS

DATE:
 1/3/23
 SCALE:
 1/4"=1'-0"
 SHEET:
B-2



FRONT ELEVATION



RIGHTSIDE ELEVATION

EXTERIOR FINISHES

1. WHITE VINYL BATTEN BOARD SIDING OVER 1/2" OSB, 4" ALUMINUM WINDOW TRIM
2. 30 YR ARCHITECTURAL SHINGLE ROOF
3. SYNTHETIC WRAPPED 10" COLUMNS
4. 8" SYNTHETIC WRAPPED COLUMNS REAR PORCH
5. BRICK FOUNDATION RAISED CONCRETE SLAB PORCHES
6. FINISH GRADE TO SLOPE AWAY FROM THE FOUNDATION
7. ROOF PITCH 10/12 MAIN ROOF, 3/12 PORCH ROOF
8. VINYL DOUBLE HUNG WINDOWS WITH FULL SCREEN, GBG

To the best of my knowledge these plans are drawn to comply with owner's and/ or builder's specifications and any changes made on them after prints are made will be done at the owner's and / or builder's expense and responsibility. The contractor shall verify all dimensions and enclosed drawing. Horton Custom Designs is not liable for errors once construction has begun. While every effort has been made in the preparation of this plan to avoid mistakes, the maker can not guarantee against human error. The contractor of the job must check all dimensions and other details prior to construction and be solely responsible thereafter.

NO.	DESCRIPTION	BY	DATE

SHEET TITLE:
ELEVATIONS

PROJECT DESCRIPTION:
UNDERWOOD HOME
Lot 62 Leigh Rd
Washington, NC 27889

DRAWINGS PROVIDED BY:

HORTON CUSTOM DESIGNS

DATE:

1/3/23

SCALE:

NTS

SHEET:

B-3



REAR ELEVATION



RIGHTSIDE ELEVATION

EXTERIOR FINISHES

1. WHITE BATTEN BOARD VINYL SIDING OVER 1/2" OSB, 4" ALUMINUM WINDOW TRIM
2. 30 YR ARCHITECTURAL SHINGLE ROOF
3. SYNTHETIC WRAPPED 10" COLUMNS FRONT PORCH
4. 8" SYNTHETIC WRAPPED COLUMNS REAR PORCH
5. BRICK FOUNDATION RAISED CONCRETE SLAB PORCHES
6. FINISH GRADE TO SLOPE AWAY FROM THE FOUNDATION
7. ROOF PITCH 10/12 MAIN ROOF, 3/12 PORCH ROOF
8. VINYL DOUBLE HUNG WINDOWS WITH FULL SCREEN, GBG

To the best of my knowledge these plans are drawn to comply with owner's and/ or builder's specifications and any changes made on them after prints are made will be done at the owner's and / or builder's expense and responsibility. The contractor shall verify all dimensions and enclosed drawing. Horton Custom Designs is not liable for errors once construction has begun. While every effort has been made in the preparation of this plan to avoid mistakes, the maker can not guarantee against human error. The contractor of the job must check all dimensions and other details prior to construction and be solely responsible thereafter.

NO.	DESCRIPTION	BY	DATE

SHEET TITLE:
ELEVATIONS

PROJECT DESCRIPTION:
UNDERWOOD HOME
Lot 62 Leigh Rd
Washington, NC 27889


DRAWINGS PROVIDED BY:

HORTON CUSTOM DESIGNS


DATE:
1/3/23

SCALE:
NTS

SHEET:
B-4




FOUNDATION PLAN
1/4"=1'-0"



CMU WALL - CONCRETE SLAB WALL DETAIL

FOUNDATION NOTES:

1. FOOTING SIZE 24"X 10"
2. FOUNDATION WALL SOLID CMU WITH BRICK EXTERIOR
3. ANCHOR BOLTS EVERY 4'
4. TWO #4 REBARS CONTINUOUS IN THE FOOTERS
5. ANY CMU WALL OVER 4' MUST HAVE #4 DOWEL RODS EVERY 4'



Thickened Slab Below Grade

NO.	DESCRIPTION	BY	DATE

SHEET TITLE:
FOUNDATION PLAN

PROJECT DESCRIPTION:
UNDERWOOD HOME
Lot 62 Leigh Rd
Washington, NC 27889

DRAWINGS PROVIDED BY:
HORTON CUSTOM DESIGNS


DATE:

1/3/23


SCALE:

SHEET:


B-5



ROOF PLAN
1/4"=1'-0"



SOFFIT-ROOF DETAIL



Vented Soffit
NOT TO SCALE


ROOFING NOTES:

1. 30 YR ARCHITECTURAL SHINGLE ROOF
2. ROOF PITCH 10/12 MAIN ROOF, 3/12 PORCH ROOF
3. 2x8 RAFTERS, 2X10 RAFTERS IN VAULTED AREAS

NO.	DESCRIPTION	BY	DATE

SHEET TITLE:
ROOFING PLAN

PROJECT DESCRIPTION:
UNDERWOOD HOME
Lot 62 Leigh Rd
Washington, NC 27889

DRAWINGS PROVIDED BY:

HORTON CUSTOM DESIGNS

DATE:




1/3/23

SCALE:


SHEET:

B-6


Kitchen Cabinets Layout



Island Cabinet Layout



Bathroom Cabinets Layout



NO.	DESCRIPTION	BY	DATE

SHEET TITLE:
DETAILS

PROJECT DESCRIPTION:
UNDERWOOD HOME
Lot 62 Leigh Rd
Washington, NC 27889

DRAWINGS PROVIDED BY:

HORTON CUSTOM DESIGNS

DATE:
1/3/23

SCALE:

SHEET:
B-7

GENERAL NOTES:

THE BUILDER SHALL VERIFY THAT SITE CONDITIONS ARE CONSISTENT WITH THESE PLANS BEFORE STARTING WORK. WORK NOT SPECIFICALLY DETAILED SHALL BE CONSTRUCTED TO THE SAME QUALITY AS SIMILAR WORK THAT IS DETAILED. ALL WORK SHALL BE DONE IN ACCORDANCE WITH INTERNATIONAL BUILDING CODES AND LOCAL CODES.

WRITTEN DIMENSIONS AND SPECIFIC NOTES SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS AND GENERAL NOTES. THE ENGINEER/DESIGNER SHALL BE CONSULTED FOR CLARIFICATION IF SITE CONDITIONS ARE ENCOUNTERED THAT ARE DIFFERENT THAN SHOWN. IF DISCREPANCIES ARE FOUND IN THE PLANS OR NOTES, OR IF A QUESTION ARISES OVER THE INTENT OF THE PLANS OR NOTES. CONTRACTOR SHALL VERIFY AND IS RESPONSIBLE FOR ALL DIMENSIONS (INCLUDING ROUGH OPENINGS).

PLEASE SEE ADDITIONAL NOTES CALLED OUT ON OTHER SHEETS.

BUILDING PERFORMANCE:

HEAT LOSS CALCULATIONS SHALL COMPLY WITH THE REQUIREMENTS OF REGIONAL AND LOCAL CODES. SEE CALCULATIONS. PORCHES, DECKS, FOUNDATION, FIREPLACE ENCLOSURES, AND GARAGE AREAS NOT INCLUDED IN LIVING AREA. ALL EXHAUST FANS TO BE VENTED DIRECTLY TO THE EXTERIOR. ALL PENETRATIONS OF THE BUILDING ENVELOPE SHALL BE SEALED WITH CAULK OR FOAM.

STRUCTURAL ENGINEER: BY OWNER
DESIGNER: HORTON CUSTOM DESIGNS
BUILDER:

FRAMING NOTES:

PROVIDE DOUBLE JSTS. UNDER ALL WALLS RUNNING PARALLEL TO JOISTS.

PROVIDE POSITIVE VENTILATION AT EA. END OF EA. RAFTER SPACE AT VAULTED CEILING AREAS.

PROVIDE FIRE BLOCKING, DRAFT STOPS AND FIRE STOPS AS PER I.B.C. SEC. R502.12.

PROVIDE POSITIVE CONECTIONS AT EACH END OF ALL POSTS AND COLUMNS TO RESIST LATERAL DISPLACEMENT.

RAILING NOTES:

STAIRWAYS SHALL HAVE A MIN. WIDTH OF 34". HAND RAILS MAY ENCROACH A MAX. OF 3 1/2" INTO THE REQUIRED WIDTH.

TREADS SHALL HAVE A MIN. WIDTH OF 9". STAIR TREADS MUST BE UNIFORM AND CAN NOT VARY FROM THE LARGEST TO THE SMALLEST BY MORE THAN 3/8".

STAIRWAYS SHALL HAVE MIN. 6'-8" OF HEADROOM AT THE NOSE OF THE STAIR.

ENCLOSED USABLE SPACE UNDER INTERIOR STAIRS SHALL BE PROTECTED ON THE ENCLOSED FACE WITH 5/8" TYPE "X" GYPSUM WALL BOARD.

STAIRWAYS SHALL HAVE AT LEAST ONE HANDRAIL LOCATED 34" TO 38" ABOVE THE NOSING OF TREADS AND LANDINGS. THE HAND GRIP PORTION OF HANDRAILS SHALL NOT BE LESS THAN 1-1/2" OR GREATER THAN 2" IN CROSS-SECTIONAL DIMENSION.

HANDRAILS SHALL BE CONTINUOUS THE FULL LENGTH OF THE STAIRS. THE ENDS OF HANDRAILS SHALL RETURN TO WALL OR TERMINATE INTO A NEWEL POST OR SAFETY TERMINAL.

STAIRWAYS HAVING LESS THAN 2 RISERS DO NOT REQUIRE A HAND RAIL.

34" MIN. HEIGHT GUARDRAILS SHALL BE PROVIDED FOR AT PORCHES, DECKS, BALCONIES, STAIRWAYS AND LANDINGS WHERE THE ADJACENT SURFACE IS GREATER THAN 24" BELOW.

RAILING AND GUARDRAIL BALUSTER SPACING SHALL BE NO GREATER THAN 4".

THE TRIANGULAR OPENINGS FORMED BY THE RISER, TREAD, AND BOTTOM OF GUARDRAIL SHALL NOT ALLOW A 6" DIAMETER SPHERE TO PASS THROUGH.

EXTERIOR SPIRAL STAIRS TO BE FABRICATED AND INSTALLED PER THE MFG. INSTRUCTIONS.

HOMEOWNER & CONTRACTOR: TO VERIFY ALL DIMENSIONS, STRUCTURAL DETAILS, AND BUILDING CODES, AND GRADE REQUIREMENTS.

FOUNDATION NOTES:

SLOPE CRAWL SPACE TO DRAIN. MAXIMUM SLOPE IS 2 HORIZ., 1 VERT. BETWEEN FOOTINGS AT DIFFERENT ELEVATIONS.

ALL FOOTINGS TO REST ON CLEAN, FIRM UNDISTURBED SOIL. STEP FOOTINGS A REQUIRED TO MAINTAIN REQUIRED DEPTH BELOW FINISH GRADES.

CONCRETE STRENGTH,
3,000 PSI AT 28 DAYS FOR ALL SLABS. (FOUNDATION DESIGN BASED ON 2,500 PSI).
3,000 PSI AT 28 DAYS FOR ALL OTHER CONDITION.
MAXIMUM SLUMP, 4"

USE ASTM A-615 GRADE 60 DEFORMED REINFORCING BARS UNLESS NOTED OTHERWISE

CONCRETE EXPASION ANCHORS SHALL BE 'SIMPSON WEDGE-ALL STUD ANCHORS' OR ENGINEER APPROVED EQUAL. EPOXY TO BE SIMPSON "SET" ADHESIVE OR APPROVED EQUAL.

INFILTRATION, ALL OPENINGS IN THE EXT. BLDG. ENVELOPE SHALL BE SEALED AGAINST AIR INFILTRATION. THE FOLLOWING AREAS MUST BE SEALED.

- * JOINTS AROUND WINDOW AND DOOR FRAMES
- * JOINTS BETWEEN WALL CAVITY AND WINDOW/DR. FME.
- * JOINTS BETWEEN WALL AND FOUNDATION
- * JOINTS BETWEEN WALL AND ROOF
- * JOINTS BETWEEN WALL PANELS
- * UTILITY PENETRATIONS THROUGH EXTERIOR WALLS

ROOF FRAMING / TRUSS NOTES:

TRUSS DRAWING IS FOR ILLUSTRATION ONLY. ALL TRUSSES SHALL BE INSTALLED & BRACED TO MANUFACTURERS DRAWINGS & SPECIFICATIONS.

ALL TRUSSES SHALL CARRY MANUFACTURERS STAMP.

ALL TRUSSES WILL NOT BE FIELD ALTERED WITHOUT PRIOR BUILDING DEPT. APPROVAL OF ENGINEERING CALCULATIONS.

ALL TRUSSES SHALL HAVE DESIGN DETAILS & DRAWINGS ON SITE FOR FRAMING INSPECTION.

ALL CONNECTIONS OF RAFTERS, JACK OR HIP TRUSSES TO MAIN GIRDER TO BE PROVIDED BY TRUSS MANUFACTURER.

ALL ROOF FRAMING 16" O.C.

ALL OVERHANGS 12".

INSTALL POLYISOCYANURATE FOAM TYPE INSULATION AT FLOOR AND PLATE LINES, OPENINGS IN PLATES, CORNER STUD CAVITIES AND AROUND DOOR AND WINDOW ROUGH OPENING CAVITIES.

ATTIC VENTILATION: REQUIRED ABOVE HOUSE.

WALL HEADERS: (2) 2 X 10 DF 2 TYP. UNO

ROOF & FLOOR TRUSS MANUFACTURER: _____

MISCELLANEOUS NOTES:

EACH BEDROOM TO HAVE A MINIMUM WINDOW OPENING OF 5.7 SQ. FT. WITH A MINIMUM WIDTH OF 20 IN. AND A SILL LESS THAN 44" ABOVE FIN. FLR.

ALL GLAZING WITHIN 18 IN. OF THE FLOOR AND/OR WITHIN 24 IN. OF ANY DOOR (REGARDLESS OF WALL PLANE) ARE TO HAVE SAFETY GLAZING. ALL GLAZING WITHIN 60 IN. OF TUB OR SHOWER FLOOR, 60 IN. OF A STAIR LANDING OR GREATER THAN 9 SQUARE FEET ARE TO HAVE SAFETY GLAZING

SKYLIGHTS ARE TO BE GLAZED WITH TEMPERED GLASS ON OUTSIDE AND LAMINATED GLASS ON THE INSIDE (UNLESS PLEXIGLASS). GLASS TO HAVE MAXIMUM CLEAR SPAN OF 25 IN. AND FRAME IS TO BE ATTACHED TO A 2x CURB WITH A MINIMUM OF 4 IN. ABOVE ROOF PLANE.

ALL TUB AND SHOWER ENCLOSURES ARE TO BE GLAZED WITH SAFETY GLASS.

ALL EXTERIOR WINDOWS ARE TO BE DOUBLE GLAZED AND ALL EXTERIOR DOORS ARE TO BE SOLID CORE WITH WEATHERSTRIPPING. PROVIDE 1/2 IN. DEADBOLT LOCKS ON ALL EXTERIOR DOORS, AND LOCKING DEVICES ON ALL DOORS AND WINDOWS WITHIN 10 FT. (VERTICAL) OF GRADE. PROVIDE PEEPHOLE 54-66 IN. ABOVE FIN. FLOOR ON EXTERIOR ENTRY DOORS.

PROVIDE ONE SMOKE DETECTOR IN EACH ROOM AND ONE IN EACH CORRIDOR ACCESSING BEDROOMS. CONNECT SMOKE DETECTORS TO HOUSE POWER AND INTER-CONNECT SMOKE DETECTORS TO HOUSE POWER AND INTERCONNECT SO THAT, WHEN ANY ONE IS TRIPPED, THEY ALL WILL SOUND. PROVIDE BATTERY BACKUP FOR ALL UNITS.

PROVIDE COMBUSTION AIR VENTS (W/SCREEN AND BACK DAMPER) FOR GAS FIRE-PLACE AND ANY OTHER APPLIANCES WITH AN OPEN FLAME.

BATHROOMS AND UTILITY ROOMS ARE TO BE VENTED TO THE OUTSIDE WITH A FAN CAPABLE OF PRODUCING A MINIMUM OF 5 AIR EXCHANGES PER HOUR.

RANGE HOODS ARE ALSO TO BE VENTED TO THE OUTSIDE.

ELECTRICAL RECEPTACLES IN BATHROOMS, KITCHENS AND GARAGES SHALL BE G.F.I. OR G.F.I.C. PER NATIONAL ELECTRICAL CODE REQUIREMENTS.

INSULATE ALL ACCESS DOORS/ HATCHES TO CRAWL SPACES AND ATTICS TO THE EQUIVALENT RATING OF THE WALL, FLOOR OR CEILING THROUGH WHICH THEY PENETRATE. UNO ON PLANS.

ATTIC	R-30
WALLS	R-15
FLOORS	R-19

PROVIDE CRAWLSPACE VENTING TO MEET THE REQUIREMENTS OF THE 2006 EDITION OF THE I.R.C.

PROVIDE SPECIAL INSPECTION, SPECIAL TESTING, REPORTING AND COMPLIANCE PROCEDURES ACCORDING TO THE 2006 INTERNATIONAL BUILDING CODE.

SPECIAL INSPECTOR QUALIFICATIONS: DEMONSTRATE COMPETENCE, TO THE SATISFACTION OF THE BUILDING OFFICIAL, FOR INSPECTION OF THE PARTICULAR TYPE OF CONSTRUCTION OR OPERATION IN QUESTION. PRIOR TO THE BEGINNING OF CONSTRUCTION, REVIEW THE SPECIAL INSPECTION REQUIREMENTS WITH THE ARCHITECT, ENGINEER, BUILDING OFFICIAL, GENERAL CONTRACTOR AND SPECIAL INSPECTORS.

DUTIES OF THE SPECIAL INSPECTOR INCLUDE, BUT ARE NOT LIMITED TO: OBSERVE THE WORK FOR CONFORMANCE WITH THE APPROVED PERMIT DRAWINGS AND SPECIFICATIONS. BRING DISCREPANCIES TO THE IMMEDIATE ATTENTION OF THE GENERAL CONTRACTOR FOR BUILDING OFFICIAL. FURNISH INSPECTION REPORTS FOR EACH INSPECTION TO THE BUILDING OFFICIAL, ARCHITECT, ENGINEER, GENERAL CONTRACTOR AND OWNER IN A TIMELY MANNER. SUBMIT A FINAL REPORT STATING WHETHER THE WORK REQUIRING SPECIAL INSPECTION WAS INSPECTED, AND WHETHER THE WORK IS IN CONFORMANCE WITH THE APPROVED PERMIT DRAWINGS AND SPECIFICATIONS.

DUTIES OF THE GENERAL CONTRACTOR INCLUDE, BUT ARE NOT LIMITED TO: NOTIFY SPECIAL INSPECTOR THAT WORK IS READY FOR INSPECTION AT LEAST 24 HOURS BEFORE THE INSPECTION IS REQUIRED. MAINTAIN ACCESS TO WORK REQUIRING SPECIAL INSPECTION UNTIL IT HAS BEEN OBSERVED AND INDICATED TO BE IN CONFORMANCE BY THE SPECIAL INSPECTOR AND APPROVED BY THE BUILDING OFFICIAL. PROVIDE THE SPECIAL INSPECTOR WITH ACCESS TO APPROVED PERMIT DRAWINGS AND SPECIFICATIONS AT THE JOB SITE. MAINTAIN JOB-SITE COPIES OF ALL REPORTS SUBMITTED BY THE SPECIAL INSPECTOR.


DEFINITIONS:
CONTINUOUS INSPECTION: THE SPECIAL INSPECTOR IS OBSERVING THE WORK REQUIRING SPECIAL INSPECTION AT ALL TIMES.
PERIODIC INSPECTION: THE SPECIAL INSPECTOR IS ON SITE AS REQUIRED TO CONFIRM THAT THE WORK REQUIRING SPECIAL INSPECTION IS IN CONFORMANCE.

--

NO.	DESCRIPTION	BY	DATE

SHEET TITLE: **GENERAL NOTES**

PROJECT DESCRIPTION: **UNDERWOOD HOME**
Lot 62 Leigh Rd
Washington, NC 27889

DRAWINGS PROVIDED BY:  **HORTON Custom Designs**

DATE:

1/3/23

SCALE:

SHEET:

B-8